

PROJECT PROFILE:



Location	Morrinton Quarry, Dumfries, Scotland
Client	Tarmac Northern Ltd
Value	£1,240,000
Duration	1 year
Quantities	270,000t single size products, 100,000t type 1 sub base, 70,000t crusher run material.
Description	<p>RJT were awarded this contract through a tender process. This contract involves producing capping materials as well as single size aggregates which are used at the on site asphalt plant as well as being transported for use in various Tarmac sites across the country.</p> <p>This site is split into two levels with the primary crushing taking place on the upper levels and the crushed material being transported to the lower levels to be screened. This site produces predominately minus 14mm aggregates so a closed circuit operation is used where the oversize material is fed directly into the tertiary crusher to achieve a greater nominal size and low aggregate flake content.</p>
Key Issues	Health, safety and environmental procedures. Safe operating procedures, Machine isolation procedures,
Reference	Mr Steven Lough, Tarmac Northern, 07702635485