

PROJECT PROFILE:



| | |
|--------------------|---|
| Location | Duntilland Quarry, Salsburgh. |
| Client | Aggregate Industries. |
| Value | £56,250 |
| Duration | 5 Weeks |
| Quantities | Re-crush 37,500t Type 1 Sub-base. |
| Description | RJT were awarded this contract through a tender process. This contract involved processing a type 1 material that had previously been produced by the quarry static plant. Due to an on going contract A.I. required additional single sized aggregates. Shape and quality were of high importance. RJT used a cone crusher with a fine head to produce a quality material. As there was a 30% dust content within the material to be processed RJT used a Finlay 694+ screener with a 20ft screen deck to ensure all dust was removed from final products. |
| Key Issues | Health, safety and environmental procedures. Safe operating procedures, Machine isolation procedures, |
| Reference | Charles McQuade Aggregate Industries 07850 307 947 |