

**PROJECT PROFILE: Leith Street, Edinburgh – Basement reduced level excavation**



<b>Location</b>	<b>Leith Street, Edinburgh City Centre</b>
<b>Client</b>	<b>Sir Robert McAlpine</b>
<b>Value</b>	£420,000.00
<b>Duration</b>	8Wks
<b>Quantities</b>	Excavation and disposal off site of 10,000 m3 of inert soils, 4,000 m3 of rock excavation, WAC Testing, 2,000 t Non haz waste off site
<b>Project Description</b>	Basement reduced level excavation.
<b>Key Issues</b>	City Centre site, traffic management and keeping existing roads clean, controlled entry and exit, interface with public, depth of excavation, temporary support systems and working with piling and support systems, existing services and diversions. Site Clearance of trees and brush 5,500 m2
<b>Principal Elements</b>	Off site contaminated and inert soils and management of receiving landfill site also a city centre site at Granton Harbour Landforming (Forth Ports) Full WAMITAB requirements and mangement
Project Reference; Commercial Reference	Bruce McEwan Sir Robert McAlpine 07889 615 739 Kevin Robinson Sir Robert McAlpine 0131 202 0279